

IFB # REBID 26-01073-3138

IFB DATE: JANUARY 7, 2026
3:00 PM LOCAL PREVAILING TIME

DEPARTMENT: HENRY COUNTY SCHOOLS
FOR: INSTALLATION OF WALK IN-FREEZER
FOR CAMPBELL COURT ELEMENTARY

[illegible]

IFB # REBID 26-01073-3138

IFB DATE: JANUARY 7, 2026
3:00 PM LOCAL PREVAILING TIME

DEPARTMENT: HENRY COUNTY SCHOOLS
FOR: INSTALLATION OF WALK IN-FREEZER
FOR CAMPBELL COURT ELEMENTARY

**DEPARTMENT: HENRY COUNTY SCHOOLS
FOR: INSTALLATION OF WALK IN-FREEZER
FOR CAMPBELL COURT ELEMENTARY**

[illegible]

Henry County School Nutrition

Vendors awarded contracts by sponsors are responsible for abiding by all applicable federal and state laws when providing goods or services. All contracts must contain certain federal provisions. Not all provisions are applicable, as some are contingent on the amount of the award or the types of services. Sponsors are ultimately responsible for ensuring all required provisions and certifications are included in their contracts.

Henry County School Nutrition is seeking bids for a custom Master-Bilt walk-in Freezer with installed Fermod shelving, for the following school:

Campbell Court Elementary School, 220 Campbell Court, Bassett, VA 24055

HCPS Maintenance provides the breakers for all electrical needs. The project will be turnkey otherwise.

A mandatory pre-bid meeting will be held at Campbell Court on December 16, 2025, at 10:00 A.M. Bids will only be accepted from vendors who send a representative to the mandatory pre-bid for this project. Please bring applicable personnel to provide input on installation of compressor and pad on rooftop and HVAC installation and start-up. Please provide pricing within the following table.

Scope of work:

Project	Requirements	Cost
Custom Master-Bilt Walk-In Freezer	Per attached specifications Option A: A2I Refrigeration Option B: R448/R449 Refrigeration	\$42,354.96 \$37,763.04
Installation of Walk-in Box, running lines, drain installation, connections & start-up.	Any required holes made in the roof / floor will be sealed to be weather-proof to avoid damage to the area where the freezer is installed.	\$14,250.00
Compressor and Pad	Secure and level compressor on roof top. Weather seal back to manufacturer's recommendations when penetrating the roof layers. Roof penetration shall be done by a person who has certification to work with Carlisle roofing manufacturer.	\$2320.00
Fermod Shelving	Per attached specifications	\$5,284.42
Assembly & Installation of Fermod Shelving	Per attached drawing & specifications	Price included with the installation.
	TOTAL	Option A: \$64,209.38 Option B: \$59,617.46